

Don't Guess it

Quanti-Quote

Incorporating

Quanti-Mate

Peter & Carol Ferguson T/A
Trewint, Main Street,
Shap,
Cumbria
CA10 3NH
Tel 01931 716810

it !

We make the quoting from architectural plans easy for you by, giving you a comprehensive materials quotation.

- ◆ Because we offer a maximum of 12 business hour turn round service it helps you to give a quick and accurate response to your customer
- ◆ It is printed on your headed paper so your customer comes back to you

Oversite materials based on :-
 150mm thick aggregate
 25mm Blinding
 Concrete 100mm thick

20mm aggregate	Tonnes	36.4
Blinding material	Tonnes	5.9
Polythene damp membrane	M2	182
1.2.4 mix concrete	M3	16.6
External soil backfill	M3	4.8

- ◆ As seen above the quantities are presented in a clear manner which facilitate ease of pricing.

Cavity insulation area Dritherm	M2	147
External render area	M2	146
Internal studwork plaster	M2	259
Internal skin plaster area	M2	120
Window only area	M2	15.2
Febmix Mortar plasticiser	Litres	9
100mm DPC Visqueen	M	197
150mm DPC Visqueen	M	78

- ◆ We incorporate your own trade brands to customise our service to you and help ensure forthcoming orders

Summary of construction
 Groundworks
 Brickwork Summary
 Ground Floor
 1st Floor
 Roof Tiling
 Joists
 Roof Timbers
 Carpenter 1st Fix
 Carpenter 2nd Fix
 Gutter
 Sanitary Ware
 Central Heating

- ◆ The quote is split up by headings which are consistent with the building process. This not only ensures vital materials are not forgotten but also effective site control of materials is maintained.
- ◆ We provide you with a comprehensive quotation from Foundation to Roof and Wall Ties to Bath Taps

ITEM 16 ROOF TIMBERS

Rafters	50 X 150	12/5.1	M	61.2
Rafters	50 X 150	12/2.1	M	25.2
Rafters	50 X 150	21/3.3	M	69.3
Rafters	50 X 150	14/.9	M	12.6
Binders	50 X 100		M	17.1
Purlins	100 X300		M	8.4
Ridge board	75 X 275		M	3.9
Purlin struts	50 X 225	6/1.8	M	21.6
Collars	25 X 150		M	9.0
Roof plates	75 X 100		M	18.0
Fascia board	19 X 175		M	18.6
Barge board	19 X 150		M	15.9
Soffit strip	300 X 6		M	34.5
Wall straps	600			8
Bearer	50 x 175		M	12.1

- ◆ Specifies materials consistent with current Building Codes

SUNDRY ITEMS NOT CALCULATED

Structural steels
 Joist Hangers
 Nails
 Screws
 Glass & Putty
 Decorative materials
 Wall tiles
 Electrical components
 External drives and paths
 Underground pipes
 Soil pipes
 Waste pipes
 Copper tube
 Copper fittings
 Lead flashings
 Patio slabs
 Fencing

- ◆ We indicate which items have not been calculated for.
- ◆ We allow for expected wastage of appropriate materials such as cement
- ◆ Full or part quantities can be done such as just the Timber or just Building Materials ,Roof Materials and Central Heating
- ◆ The program we use is tried and tested and used by Large National Merchants
- ◆ Utilises standard types and sizes of materials commonly used for residential buildings.

Contact Peter on 01931 716810 for more information.

See our Internet Site <http://www.quantiquote.co.uk> or e-mail Peter@quantiquote.co.uk

